

名	称	井上11号線道路補修工事
箇	所	吉野川市山川町井上

[illegible]

数量総括表 (2/2)

名 称	井上11号線道路補修工事
箇 所	吉野川市山川町井上

[illegible]

道 路 土 工 計 算 書											
測 点	点 間 距 離	掘 削 (表土)									備 考
		断 面	平 均	数 量	断 面	平 均	数 量	断 面	平 均	数 量	
NO. 0 - 0.20		0.0									
NO. 0 + 0.60	0.80	0.2	0.10	0.1							W=0.95m t=0.2m
NO. 0 + 1.70	1.10	0.5	0.35	0.4							
NO. 0 + 3.10	1.40	0.5	0.50	0.7							N0.0 +1.70断面 流用
NO. 0 + 7.20	4.10	0.2	0.35	1.4							W=0.95m t=0.2m
NO. 0 + 8.20	1.00	0.1	0.15	0.2							
NO. 0 + 8.60	0.40	0.1	0.10	0.0							W=0.30m t=0.2m
	m			m3							
合 計	8.80			2.8							

道 路 土 工 計 算 書											
測 点	点 間 距 離	埋 戻 し (表土)									備 考
		断 面	平 均	数 量	断 面	平 均	数 量	断 面	平 均	数 量	
NO. 0 - 0.20		0.0									
NO. 0 + 0.60	0.80	0.1	0.05	0.0							W=0.40m t=0.2m
NO. 0 + 1.70	1.10	0.1	0.10	0.1							
NO. 0 + 3.10	1.40	0.1	0.10	0.1							N0.0 +1.70断面 流用
NO. 0 + 7.20	4.10	0.1	0.10	0.4							W=0.40m t=0.2m
NO. 0 + 8.20	1.00	0.1	0.10	0.1							
NO. 0 + 8.60	0.40	0.1	0.10	0.0							W=0.30m t=0.2m
	m			m3							
合 計	8.80			0.7							

道 路 土 工 計 算 書											
測 点	点 間 距 離	床 堀 り (基盤土)			埋 戻 し (基盤土)						備 考
		断 面	平 均	数 量	断 面	平 均	数 量	断 面	平 均	数 量	
NO. 0 - 0.50		0.0			0.0						
NO. 0 + 0.60	1.10	0.3	0.15	0.2	0.3	0.15	0.2				N0.0 +1.70断面 流用
NO. 0 + 1.70	1.10	0.3	0.30	0.3	0.3	0.30	0.3				
NO. 0 + 3.10	1.40	0.3	0.30	0.4	0.3	0.30	0.4				N0.0 +1.70断面 流用
NO. 0 + 7.20	4.10	0.3	0.30	1.2	0.3	0.30	1.2				N0.0 +1.70断面 流用
NO. 0 + 8.20	1.00	0.3	0.30	0.3	0.3	0.30	0.3				
NO. 0 + 8.60	0.40	0.3	0.30	0.1	0.3	0.30	0.1				N0.0 +8.20断面 流用
A部	0.40	0.4		0.2	0.3		0.1				
路盤部	2.60	0.03		0.10							W=0.30m t=0.10m
	0.90	0.04		0.00							W=0.40m t=0.10m
	m			m3			m3				
合 計	13.00			2.8			2.6				

構 造 物 撤 去 工 計 算 書						
名 称	規 格 ・ 細 別		算 式		単位	小 計 合 計
Co構造物取壊し	無筋構造物					
	現況堡壁①	機械	0.06 × 2.80		m ³	0.17
	現況堡壁②	機械	0.04 × 6.90		m ³	0.28 0.45
	嵩上部	人力	0.01 × 0.55		m ³	0.01 0.01
舗装版破碎	アスファルト版	t=4cm	0.30 × 3.90		m ²	1.17
	〃		0.40 × 0.90		m ²	0.36 1.53
	コンクリート版	t=15cm	(0.40 + 0.40) × 1/2 × 1.60		m ²	0.64
	〃		(0.40 + 0.30) × 1/2 × 4.70		m ²	1.65
	〃		(0.30 + 0.30) × 1/2 × 0.65		m ²	0.20 2.49
舗装版切断	アスファルト版	t=4cm	5.10		m	5.10
	コンクリート版	t=15cm	7.25		m	7.25
殻運搬処理	コンクリート殻・無筋	現況堡壁	0.45 + 0.01		m ³	0.46
	〃	コンクリート版	2.49 × 0.15		m ³	0.37 0.83
	アスファルト殻	t=4cm	1.53 × 0.04		m ³	0.06 0.06
	建設汚泥	アスファルト版	5.10 × 0.04 × 2.30 × 0.01		m ³	0.005
	コンクリート版		7.25 × 0.15 × 6.50 × 0.01		m ³	0.071 0.08

堡 壁 コ ン ク リ ー ト 計 算 書														
測 点	高さH (m)	距離	コンクリート			型 枠			基礎碎石			備 考		
		(m)	断 面	平 均	数 量	断 面	平 均	数 量	断 面	平 均	数 量			
NO. 0	0.344		0.052			0.69			0.35			平均H	累計H	
NO. 0 + 0.13	0.600	0.13	0.090	0.0710	0.009	1.20	0.945	0.12	0.35	0.350	0.05	0.472	0.06	
NO. 0 + 1.70	0.600	1.57	0.090	0.0900	0.141	1.20	1.200	1.88	0.35	0.350	0.55	0.600	0.94	
NO. 0 + 1.70 ’	0.450	0.00	0.068	0.0790	0.000	0.90	1.050	0.00	0.35	0.350	0.00	0.525	0.00	
NO. 0 + 3.70	0.450	2.00	0.068	0.0680	0.136	0.90	0.900	1.80	0.35	0.350	0.70	0.450	0.90	
NO. 0 + 3.70 ’	0.600	0.00	0.090	0.0790	0.000	1.20	1.050	0.00	0.35	0.350	0.00	0.525	0.00	
NO. 0 + 6.70	0.600	3.00	0.090	0.0900	0.270	1.20	1.200	3.60	0.35	0.350	1.05	0.600	1.80	
NO. 0 + 8.20	0.583	1.50	0.087	0.0885	0.133	1.17	1.185	1.78	0.35	0.350	0.53	0.592	0.89	
	平均高H	m			m3			m2			m2		m	
合 計	0.560	8.20			0.689			9.18			2.88		4.59	
目 地 材	0.689 ×1/10= 0.07 m²													

[illegible]

[illegible]